



PLAN DETAIL NOTES

NOTE 1 5/8" FOIL-BACKED DRYWALL, ROOM 45. GLASS MESH MORTAR UNITS COVERED WITH CERAMIC TILE, ROOM 54. EXTEND DRYWALL, ROOM 45, TO ROOF DECK. EXTEND GLASS MESH MORTAR UNITS, ROOM 54, TO ABOVE CEILING. ABOVE CEILING TO ROOF DECK PROVIDE 5/8" FOIL-BACKED DRYWALL.

NOTE 2 METAL EDGE TRIM AND SEALANT TO FORM CONTROL JOINT.

