



STAGE FLR.

101'-4"



(2) LAYERS 3/4" FRT PLYWOOD
TOP PLATE CUT TO FOLLOW
WALL CURVE.

OAK BULLNOSE TRIM, CUT TO FOLLOW
CURVE OF WALL. INSTALL 1/4 X 1 1/2 TRIM
PIECE ON STAGE SIDE.

1 1/2" X 1 1/2" X 1/4" ANGLES AT 32" O.C.
EXPANSION BOLT TO CONCRETE WITH
(2) 1/2" X 4" EXPANSION ANCHORS.
PROVIDE 1 1/2" X 1/4" X 3" TOP PLATE
WELDED TO ANGLE FOR CONNECTION
TO PLYWOOD TOP PLATE WITH (2) 1/4"
X 1" LAG BOLTS.

1X6 OAK TRIM WITH EASED
EDGE

1/4" BIRCH VENEER PLYWOOD
INSTALLED OVER 5/8" GWB.

1/2" X 1" OAK TRIM WITH EASED EDGES
INSTALLED OVER 3/4" X 3/4" OAK EDGES
TRIM

(1) LAYER OF 1/4" OAK VENEER
PLYWOOD OVER (2) 1/4" LAYERS OF
PARTICLE BOARD.

1'-4" SQUARE

3 5/8" METAL STUDS AT 16" O.C. MIN.
OVERHANG EDGE OF THEATER FLOOR 1
5/8". INSTALL WITH CONTINUOUS CURVED
BOTTOM AND TOP TRACKS.

1X6 OAK TRIM WITH EASED
EDGE

THEATER FLR.

98'-0"



1 5/8" METAL STUDS AT 16" O.C.
WITH CONTINUOUS TOP AND
BOTTOM TRACKS

WATERPROOFING (07170)

SCHEDULED BASE

ORCH. PIT FLR.

95'-1"



SUB-DRAIN (02620)

E4
A7.3

ORCHESTRA PIT DETAIL

1 1/2"=1'-0"